| No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | |
| 3 | Size stone (burnt) in surki mortar .. .. | C.ft. | 0 5 0 | 1,873 | |
| 4 | Pointing with cement mortar .. .. | Sqr. | 4 0 0 | 16·1 | |
| 5 | Burnt stone slabs 6″ thick dressed .. .. | Sq.ft. | 0 5 0 | 404 | |
| 6 | Rough stone work new for apron .. .. | C.yd. | 1 8 0 | 255 | |
| 7 | Removing and resetting old stone apron with new jelly backing and wedging .. .. | C.yds. | 0 8 0 | 70 | |
| 8 | Dismantling old stone masonry .. .. | L. S. | Rupees | | |
| 9 | Providing joggle joints 8 feet, etc. .. .. | Each | 0 12 0 | 22 | |
| | Total for Right Flank weir .. | | | | .. |
| | *IV. Constructing a new Left Flank Weir 210 feet long at R. L. 51·00.* | | | | |
| 1 | Excavating draft and approaches .. .. | C.yd. | 0 3 0 | 3,111 | |
| 2 | Excavating foundations and filling in .. | C.yd. | 0 3 0 | 121 | |
| 3 | Stone jelly concrete in surki mortar .. .. | C.ft. | 0 4 0 | 544 | |
| 4 | Rough stone (burnt) in surki mortar .. .. | C.ft. | 0 4 0 | 692 | |
| 5 | Rough stone work for apron, new .. .. | C.yd. | 1 8 0 | 28 | |
| 6 | Removing and resetting old stone work for apron with new jelly .. .. .. | C.yd. | 0 8 0 | 58 | |
| 7 | Pointing with cement mortar .. .. | Sqr. | 3 8 0 | 10·58 | |
| 8 | Dismantling old masonry .. .. .. | L. S. | Rupees | | |
| | Total for Left Flank weir .. | | | | .. |

P. RAJAGOPALAN,
*Executive Engineer.*

## HASSAN DIVISION.

*Abstract Notification dated 25th August 1936.*

The attention of the public is hereby invited to the detailed Notification calling for tenders for restoring Rajagere Voddu, Register No. 589 of Belur Taluk, published in page 1364, Part VI of the *Mysore Gazette*, dated 3rd September 1936. The last date for the receipt of tenders is 22nd September 1936.

---

*Notification dated 31st August 1936.*

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Hassan Division, up to 24th September 1936 up to 2 P.M., for constructing two additional rooms for the Government High School building at Hassan. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of February 1937.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Hassan, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 200 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing two additional rooms for the Government High School at Hassan," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond: in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiry regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates once tendered will not be enhanced on any account.

10. Rates for non-tendered and non-estimated items shall be as per schedule rates of the Department or those fixed by the Executive Engineer after working out data with not more than 10 per cent for contractor's profit.

11. In all matters not specifically provided for and in all matters of dispute about rates, quantities, measurements, quality of works, etc., and in all disputes of any kind, the decision of the Executive Engineer will be final and legally binding.

12. Quotations must be given in words as well as in figures and they must be in specific term of unit shown against each item of work. Any quotation quoted at so much percentage less or more than estimated rate will not be accepted.

Abstract estimate for constructing additional rooms for the High School Building at Hassan.

| No. | Items of work | Unit | Rate | Quantity | Cost |
|---|---|---|---|---|---|
| | | | Rs. a. p. | | |
| | FOR 2 BLOCKS. | | | | |
| 1 | Earthwork excavation for foundation and filling in basement | C.yd. | 0 3 0 | 84 | |
| 2 | Burnt stone jelly concrete in lime mortar | C.ft. | 0 4 0 | 1,134 | |
| 3 | Size stones in lime mortar | C.ft. | 0 5 0 | 1,608 | |
| 4 | Burnt brick in lime mortar | C.ft. | 0 5 0 | 2,382 | |
| 5 | Burnt stone slabs 6″ thick dressed and fixed in lime mortar | Sq.ft. | 0 8 0 | 408 | |
| 6 | Plastering with lime mortar | Sqr. | 4 0 0 | 36·12 | |
| 7 | White washing 2 coats | | 0 4 6 | 36·12 | |
| 8 | Teakwood doors with panelled shutters $1\frac{1}{4}$″ to $1\frac{1}{2}$″ thick with bolts, clamps, etc., complete | S.ft. | 2 0 0 | 60 | |
| 9 | Teakwood windows with battened shutters outside and glazed shutters inside (without iron bars), etc., complete | S.ft. | 2 8 0 | 150 | |
| 10 | Teakwood glazed ventilators with iron bars, etc., complete | S.ft. | 1 8 0 | 54 | |
| 11 | Teakwood sunshades as per specification | Each. | 10 0 0 | 6 | |
| 12 | Providing and fixing cut stone pillars with base and capital as per specification | Each. | 20 0 0 | 6 | |
| 13 | Teakwood wrought and put up with 2 coats of wood oiling | C.ft. | 4 8 0 | 60·14 | |
| 14 | Preparing and fixing king post Truss as per specification | Each. | 30 0 0 | 4 | |
| 15 | Roofing with 1st class Mangalore tiles on teakwood reepers | Sqrs. | 24 0 0 | 16·06 | |
| 16 | Ridge tiles set in mortar with cement pointing | R.ft. | 0 8 0 | 51 | |
| 17 | Providing and fixing Teakwood ornamental eave board 9″ with chocolate painting | R.ft. | 0 8 0 | 51 | |
| 18 | Flooring with burnt stones slabs $2' \times 2' \times \frac{1}{4}'$ dressed over a bed of sand 6″ thick with cement pointing | Sqrs. | 40 0 0 | 9·36 | |
| 19 | Chunam mortar bands at gable ends | R.ft. | 0 2 0 | 42 | |
| 20 | Cornice work 9″ thick as per specification | R.ft. | 0 10 0 | 144 | |
| 21 | Chocolate painting 2 coats | Sqr. | 3 0 0 | 5·78 | |
| 22 | Pointing to basement in cement mortar 1 : 4 | Sqrs. | 4 0 0 | 3·02 | |
| 23 | Levelling the ground, etc. | | L. S. | Rs. 92 | |

N. LAKSHMINARASIMHAIYA,
*Executive Engineer.*